

जा.क्र. उर्विम/मुळदे/350/२०२०

उद्यानविद्या महाविद्यालय, मुळदे

ता. कुडाळ, जि. सिंधुदुर्ग.

दि. 13 FEB 2020

प्रति,

महाराज,

विषय :- महाविद्यालयाच्या वसतिगृहाच्या मेन गेटच्या डागडुजीचे दरपत्रक सादर करणेबाबत

वरील विषयाबाबत असे कळविण्यात येते की, उद्यानविद्या महाविद्यालय, मुळदे करीता खालीलप्रमाणे वसतिगृहाच्या मेन गेटच्या डागडुजीच्या कामाचे दरपत्रक मागविण्यात येत आहे.

अ.क्र.	कामाचे नाव	शेरा
१.	महाविद्यालयाच्या वसतिगृहाच्या मेन गेटची डागडुजी करणे.	सोबत जोडलेल्या परिशिष्ट अ मध्ये आवश्यक बाबींचे मविस्तर तपशिल, मोजमाप, प्रति रक्कम दर व रक्कम नमुद करणेत आली आहे. सदर परिशिष्ट 'अ' मधील दरच्या वर/खाली टक्केवारी नमुद करावी.

याबाबत आगाम वित्ती करण्यात येते की, कृपया आपण वरील तपशिलाप्रमाणे वसतिगृहाच्या मेन गेटच्या डागडुजीच्या कामाचे दर नमुद करून याबाबतचे दरपत्रक या कार्यालयात दि. २७/०२/२०२० प्राप्त होईल अशा तऱ्हेने सादर करावे. उशिरा प्राप्त होण्याच्या दरपत्रकाचा विचार केला जाणार नाही याची कृपया नोंद घ्यावी.

दरपत्रकाबाबत अटी खालीलप्रमाणे.

- १) दरपत्रक बंद लखोट्यातून सादर करावे व त्यावर " वसतिगृहाच्या मेन गेटच्या डागडुजीच्या कामाचे दरपत्रक " असे स्पष्ट नमुद करावे.
- २) दरपत्रकातील दर हे उद्यानविद्या महाविद्यालय, मुळदे ता. कुडाळ कार्यालयास पोहोच देण्याचे असावे.
- ३) दरपत्रक सहयोगी अधिष्ठाता, उद्यानविद्या महाविद्यालय, मुळदे ता. कुडाळ, जि. सिंधुदुर्ग - ४१६५२० या पत्त्यावर पाठवावे.
- ४) दरपत्रकात या दरपत्रकाच्या संदर्भाचा उल्लेख असावा.
- ५) टपालद्वारे दरपत्रक पोहोचण्यास विलंब झाल्यास हे कार्यालय जबाबदार राहणार नाही.
- ६) सर्व दरपत्रके मंजूर अथवा नमंजूर करण्याचा अधिकार या कार्यालयाने राखून ठेवला आहे.
- ७) दरपत्रकावर बन्धू व सेवा कर नोंदणी कर्मांक असणे अनिवार्य आहे.

आपला विरवामू

सहयोगी अधिष्ठाता

उद्यानविद्या महाविद्यालय, मुळदे

ता. कुडाळ, जि. सिंधुदुर्ग

प्रत - प्रभारी अधिकारी कृषि ज्ञान व्यवस्थापन केंद्र, डॉ. या.सा.को.कृ.वि. दापोली यांना वित्ती करण्यात येते कि, उपरोक्त दरपत्रक मागणीवर विद्यापीठ संकेतस्थळावर मुदतीत प्रसिध्द करण्यात यावे.

DR. BALASAHEB SAWANT KONKAN KRISHI VIDYAPEETH, DAPOLI  
**ABSTRACT SHEET**

Name of the Work:- Repair And Renovation Of Compound Gate Of Girls Hostel At College Of Horticulture, Mulde Tal-Kudal Dist- Sindhudurg.

**Building Proper Work Portion - A**

Item No	Item of work	SSR 2019-20 Item No	Quantity	Rate	Unit	Amount
1	Removing wire fencing with wooden post and stacking the material with all leads, lifts etc. complete.	378 / 46.24	7.20	44.00	Rmt	316.80
2	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	378 / 46.15	1.00	9.90	Nos	9.90
3	Excavation for roadway in hard murum and boulder including dressing section to the required grade, camber and side slopes and conveying the excavated materials with all lifts upto a lead of 50m. and spreading for embankment or stacking as directed.	27 / 2.13	1.23	410.00	Cum	435.30
4	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete.	201 / 21.40	0.54	1655.30	Cum	893.86
5	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc	226 / 24.04	0.39	6445.32 6380.03	Cum	2513.25 2488.21
6	Providing structural steel work in hollow section of various thickness and sizes in square, rectangular and round shape from 25mm to 450mm section as per IS 4923 YST 310 Grade produced from iron ore and blast furnace route etc. as per detailed designs and drawing or as directed including cutting, fabricating, hoisting, erecting, fixing in position, making riveted/bolted/welded connections and painting complete.	225 / 23.12	0.1481	104796.16	M.T	15520.31
7	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	223 / 23.01	0.1824	81360.66	M.T	14840.18

ASO



परिशिष्ट 'अ'

Item No	Item of work	SSR 2019-20 Item No	Quantity	Rate	Unit	Amount
8	Providing laterite stone masonry in cement mortar 1:6 in substructure and plinth including racking out joints when plastering is to be done / striking joints when no plastering is to be done watering and scaffolding.	Circular	0.18	6108.33	Cum	1099.50
9	Providing laterite stone masonry in cement mortar 1:6 in superstructure including racking out joints when plastering is to be done / striking joints when no plastering is to be done watering and scaffolding.	Circular	0.50	6781.53	Cum	3390.77
10	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed), with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	106 / 26.23	0.29	6445.52 6380.03	Cum	1869.20 1850.21

Total in Rs. 40695.5  
40545.04


Royalty & Testing Charges Work Portion - B

11	Providing royalty charges for H.B. Metal, & Murum as fixed by Government of Maharashtra. (Limited to this amount but paid periodically as per Challan bill submitted by the contractor)	Circular	0.54 0.08	144.16	Cum	77.85 11.53
12	Providing royalty charges for Sand as fixed by Government of Maharashtra. (Limited to this amount but paid periodically as per Challan bill submitted by the contractor)	Circular	0.38 0.37	158.29	Cum	58.57 60.15


Total Rs. 71.68


Note:- Estimate Prepared as Per SSR 2019-20 (w.e.f. 1-7-2019)

136.42

  
P.S. Chougale  
Junior Engineer  
College of Horticulture,  
Mulde.

Sectional Engineer  
Works - South Sub Division,  
Dr. B. S.K.K.V., Dapoli

  
Assistant Engineer  
Works - South Sub Division,  
Dr. B. S.K.K.V., Dapoli

  
University Engineer,  
Dr. B. S.K.K.V., Dapoli

Technically Scrutinised

by P.A. Nark

Sectional Engineer

DBSKKV Dapoli, Dist. Ratnagiri

Checked By S.O. Mehta  
Mioy  
14.1.2020

14/1/2020